

PRICE BID

REPAIR/RESTORATION OF OFFICE BUILDING OF MRT DIVISION, BHADRAK Tender Notice No-17535 dt 16.11.11

Sl. No.	Description Of Item	Unit	Quantity	Quoted Rate(Rs)
1	Dismantling and removing 2.5 cm thick artificial stone flooring including stacking the useful materials for reuse & removing the debris within 50 mtr initial lead etc complete	SqrMtr	101.32	
2	Dismantling and removing RCC Chajja, Shelves finns and parapet including stacking the useful materials for reuse & removing the debris within 50 mtr initial lead etc complete	SqrMtr	9.52	
3	Dismantling brick or stone masnory in cement mortar under 3.00 mtr height including stacking the useful materials for reuse & removing the debris within 50 mtr initial lead etc complete			
4	Dismantling and removing 2.5 cm thick grading concrete including stacking the useful materials for reuse & removing the debris within 50 mtr initial lead etc complete	SqrMtr	102.75	
5	Removing old lime or cement plaster from walls including racking out joints 12 mm deep & removing the debris within 50 mtr initial lead etc complete	SqrMtr	194.98	
6	Fitting & fixing of M.S Grills fitted & fixed in verandah and outside using 35mmx35mm and 25mmx25mm Angles and square bars including all material, labour, fabrication cost complete.	Kg	353.64	
7	16 mm thick cement plaster(1:6) using over brick masnory including all cost carriage royalty taxes of all materials but excluding transportation charges of cement & extra cost of cement etc complete.	SqrMtr	96.43	
8	Cement concrete(1:2:4) using 12mm size C.B.G. Chips in F&P including all cost, carriage, royalty taxes etc complete excluding T.C. of cement & E. Cost for cement etc.	Cum	4.72	

8	Fixing vitrified tiles in floors treads or steps and landing on 25 mm thick bed of cement mortar 1:1(Cement:1Sand:1) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing complete including cost of precast tiles etc. complete	Sq.mtr	69.07	
9	Fixing vitrified tiles in Dado skirting and riser of steps on 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing complete including cost of precast tiles etc. complete	Sq.mtr	14.44	
10	4 cm thick grading concrete(1:2:4) on roof slab using 12mm size crusher broken chips including all cost carriage royalty taxes of all materials etc. complete	Sq.mtr	100.68	
11	Water proofing chemical laying above grading concrete using BLAZE MAKHITOSH chemicals including cost of chemical&labour charges for application on the roof ceiling,chajja, and grading area etc. complete	Sq.mtr	49.56	
12	Finishing wall surface with Acrylic wall putty(water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P etc complete	Sq.mtr	179.14	
12	Wall painting two coats with plastic emulsion paints of approved shed on new work to give an even shed including cost of paint etc complete	Sq.mtr	1245.42	
13	Finishing walls with all weather coat of approved shade on new work,two coat to give an even shed including cost of cement paint etc complete	Sq.mtr	167.22	
14	Add for repairing of Door & Window shutter including cost of fittings	LS		
15	Add for painting the Door & Window including all labour & material cost etc complete	LS		

16	Fitting & fixing of Alluminium Doors with 6 mm black glass as per specification.	LS		
17	Alluminium Doors with 6 mm black glass as per specification.	Sq.mtr	10.57	
18	Add for development of court yard with 35x35mm size angle iron purlins and trusses to receive G.C.I. Sheet roofing including the cost of angle iron & GCI Sheet,all labour charges and L hook washer etc.	LS		
19	Add for other unforeseen items,such as plinth protection of existing building,transportation charges of cement,excalation of price for labour or material during the work etc complete(Payment will be made as per actual)	LS		
	Total Amount(Rs)			

Signature of Tenderer weith seal

GENERAL MANAGER(WORKS)
NESCO,BALASORE